13. Details of work :—	Quantity.
(1) Supplying, fixing and wiring Teakwood board 27″×21″×1″ with battens and rear board, equipping it with two iron clad S. P. Home Office Type cut-outs 50-Amps. using No. 8 B. & S. 2,500 Megohm grade insulated wire and accessories	No. 1
(2) Do 24″×18″×1″ with back board and battens, etc., equipping it with a 50-amp. D. P. automatic time switch, self wound, 220-volts, 60-cycles, two D.P.S.T. iron clad switches 15-amp. with fuses using No. 8 and 10 B. & S., 2,500 Megohm grade insulated wires and accessories	No. 1
(3) Running mains with No. 8 B. &. S. twin conductor L.C. cable using T.W. fillets of suitable size and $\frac{3}{8}$″ thick and accessories	Ft. 55
(4) Supplying, fixing and wiring in twin and triple conductor lead covered cables No. 10 and 14 B. & S. run on T.W. fillet of adequate size and $\frac{3}{8}$″ in thickness for mains and taps respectively for combined switch and wall plugs complete with nipple using one 5-amp. adaptable fuse cut-outs metal junction boxes and accessories	No. 12
(5) Supplying, fixing and wiring for wall plugs complete with 5-amp. control switch and one 5-amp. adaptable fuse cut-outs as per specification above	No. 20
(6) Do do strip lights complete with copper reflectors electro-plated 4-strip light lamps 230-volts, 60-watts 11 3/16″ long with sockets, etc., as per specification above	No. 6
(7) Do twin and triple conductor No. 14 B. & S. L.C. cables for ceiling fans 230-volts, 60-cycles, 60″ sweep, 3 or 4 blades complete with canopy, downrod, 5-speed wall type regulator clamps one 5-amp. adaptable fuse cut-out and accessories, as per specification above	No. 4
(8) Supplying and fixing lamps 200-watts. 230-volts, B.C. pearl.	No. 14
(9) Earthing	Item.

A. C. MUNIRATNA MUDALIYAR,
Superintendent.

MYSORE RAILWAYS, MYSORE.

Notification dated the 11th August 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executive Engineer, Mysore Railways, Mysore, on any working day up to 3 P.M., till Monday the 14th September 1936 for Constructing an additional Stores Building in the Central Workshops area at Mysore. Approximate estimates of quantities are given in the accompanying Schedule. The quantities are not guaranteed. The work should be completed before the end of March 1937.

2. Detailed estimates, plans, specifications, conditions of works and conditions of Schedule Agreement may be seen at the Senior Executive Engineer's Office, Mysore Railways, Mysore, on all working days between 2-30 P.M., and 4-30 P.M. When in doubt the tenderers should always ask for particulars and details.

3. Tenders should be submitted on Printed forms, which should be obtained in ample time from the Senior Executive Engineer's Office on production of a receipt for payment of rupee one to the Auditor, Mysore Railways, Mysore.

4. Every tender must be accompanied by an earnest money of Rs. 250 which should be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender and should be superscribed " Tender for Constructing an additional Stores Building " in the Central Workshops area at Mysore ", in default of which the tenders will be rejected. Tenderers who have not done work previously in this Department should produce certificates from authorities regarding their capacity for work and execution.

5. The earnest money of the rejected tenders will be returned as early as possible after the tenders are disposed of, and in the case of the accepted tender, it will be held as a part-security deposit under Clause 4 of the Schedule Agreement referred to in Para 8.

6. The final acceptance of any tender will rest with the Agent, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender or any portion of a tender.

7. The name of the contractor, whose tender has been accepted, will be posted on the Notice Board in the Senior Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful tenderer is required to execute the usual Schedule Agreement, in default of which his tender will be considered as cancelled and the earnest money forfeited to Government.

9. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much per cent less or more than the estimated rates will not be accepted.

10. Rates once tendered cannot be enhanced on any account. Rates for non-tendered and non-estimated items shall be as per average Schedule of Rates of the Railway Department or those fixed by the Senior Executive Engineer after working out data with 10 per cent for contractor's profit.

11. The whole of the work specified in the Agreement should be completed as specified in Para 1 above. Failing which or failing to carry out any of the conditions in the Agreement, the whole of the money held in deposit or so much of it as the Agent, Mysore Railways, considers proper will, without prejudice to any other legal or equitable right or remedy which the Agent may have, be absolutely forfeited to the Agent, Mysore Railways, Mysore.

12. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any item of work or specification, the decision of the Superintendent, Way and Works, Mysore Railways, Mysore, shall be final.

13. The accepted tenderer must make his own arrangements in advance for payment of Royalties, etc., in case he quarries stone, earth, kunkar, sand, etc., from Railway, Government or Forest land for use on this work, as this Department will not concern itself regarding the payment, recovery, etc.

14. Works should be executed in general as per Marryat's Specifications.

15. Contractors should make their own arrangements for the supply of water.

16. It should be noted that the quantities noted in the Schedule for doors, windows and ventilators are inside clear dimentions only.

Schedule.

Sl. No.	Particulars	Unit	Quantity
1	Earthwork excavating for foundations in all soils including hard rock, if any, filling in the basement in 6″ layers including watering and consolidating charges, conveying the surplus spoil to places shown by the Department up to a maximum lead of 500 feet and spreading it evenly as per levels fixed by the Department	1,000 C.ft.	4,000 C.ft.
2	Concrete broken stone in sand mortar	100 C.ft.	1,270 C.ft.
3	Coursed rubble masonry in sand mortar, first class, including bond stones and dressing corner stones of walls	100 C.ft.	2,300 C.ft.
4	Burnt brick in prepared mud	100 C.ft.	5,700 C.ft.
5	Burnt brick in sand mortar	100 C.ft.	600 C.ft.
6	Supplying and fixing in sand mortar burnt stone slabs 6″ thick roughly dressed	S.ft.	300 S.ft.
7	Supplying and fixing in sand mortar, burnt stone slabs 6″ thick two lines dressed	S.ft.	40 S.ft.
8	Cutting grooves in 6″ thick burnt stone slabs	Each.	8
9	Cement concrete slabs including necessary wooden framework for laying concrete, hoisting and fixing in position and fixing of bolts (cement will be supplied by the Department) ..	100 C.ft.	160 C.ft.
10	Conveying, hoisting and fixing in position cast iron cantilever brackets which will be supplied by the Department ..	Each.	21
11	Conveying, assembling, revetting, hoisting and fixing in position 20 feet span trusses, purlins, etc.	Cwt.	140 Cwt.
12	Conveying, hoisting and fixing in position 22 B. W. G. Galvanised iron corrugated sheets, ridge sheets sky lights, wind ties, etc., complete, including fixing glasses for sky lights with contractor's putty	100 S.ft.	7,500 S.ft.
13	Chunam plastering	100 S.ft.	12,400 S.ft.
14	Chunam pointing	100 S.ft.	600 S.ft.
15	White and color washing, two coats	100 S.ft.	13,000 S.ft.
16	Teakwood doors with 1½″ thick battened shutters including brass hasps and staples, brass handles, etc., complete ..	S.ft.	165 S.ft.
17	Teakwood windows with 1½″ thick battened shutters and 1″ diameter iron bars inside and fixed Expanded metal shutters outside including brass handles, etc., complete ..	S.ft.	216 S.ft.

Sl. No.	Particulars	Unit	Quantity
18	Conveying from Stores, hoisting and fixing in position Teakwood windows	Each.	4
19	Teakwood ventilators with glazed shutters and one inch diameter iron bars inside and fixed expanded metal shutters outside	S.ft.	156 S.ft.
20	Silicate painting two coats, Paint and Linseed oil will be supplied by the Department	100 S.ft.	5,700 S.ft.
21	Revetment with size stones on the face and rough stone backing as per specifications	100 C.ft.	3,000 C.ft.
22	Unloading steel and other materials from wagons including lead	Ton.	17 tons.

Notification dated the 15th August 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executive Engineer, Mysore Railways, Mysore, on any working day up to 3 P.M., till Monday the 14th September 1936 for Constructing the Depot Store Keeper's Office in the Central Workshops area at Mysore. Approximate estimates of quantities are given in the accompanying Schedule. The quantities are not guaranteed. The work should be completed before the end of February 1937.

2. Detailed estimates, plans, specifications, conditions of works and conditions of Schedule Agreement may be seen at the Senior Executive Engineer's Office, Mysore Railways, Mysore, on all working days between 2-30 P.M., and 4-30 P.M. When in doubt, the tenderer should always ask for particulars and details.

3. Tenders should be submitted on printed forms, which should be obtained in ample time from the Senior Executive Engineer's Office on production of a receipt for payment of Rupee one to the Auditor, Mysore Railways, Mysore.

4. Every tender must be accompanied by an earnest money of Rs. 250 which should be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender and should be superscribed "Tender for Constructing the Depot Store Keeper's Office in the Central Workshops area at Mysore", in default of which the tenders will be rejected. Tenderers who have not done work previously in this Department should produce certificates from authorities regarding their capacity for work and execution.

5. The earnest money of the rejected tenders will be returned as early as possible after the tenders are disposed of, and in the case of the accepted tender, it will be held as a part-security deposit under Clause 4 of the Schedule Agreement referred to in Para 8.

6. The final acceptance of any tender will rest with the Agent, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender or any portion of a tender.

7. The name of the contractor, whose tender has been accepted, will be posted on the Notice Board in the Senior Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful tenderer is required to execute the usual Schedule Agreement, in default of which his tender will be considered as cancelled and the earnest money forfeited to Government.

9. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much per cent less or more than the estimated rates will not be accepted.

10. Rates once tendered cannot be enhanced on any account. Rates for non-tendered and non-estimated items shall be as per average schedule of rates of the Railway Department or those fixed by the Senior Executive Engineer after working out data with 10 per cent for contractor's profit.

11. The whole of the work specified in the Agreement should be completed as specified in Para 1 above; failing which or failing to carry out any of the conditions in the Agreement, the whole of the money held in deposit or so much of it as the Agent, Mysore Railways, considers proper, will, without prejudice to any other legal or equitable right or remedy which the Agent may have, be absolutely forfeited to the Agent, Mysore Railways, Mysore.

12. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any item of work or specification, the decision of the Superintendent, Way and Works, Mysore Railways, Mysore, shall be final.

13. The accepted tenderer must make his own arrangements in advance for payment of Royalties, etc., in case he quarries, stone, earth, kunkar, sand, etc., from Railway, Government or Forest land for use on this work, as this Department will not concern itself regarding the payment, recovery, etc.

14. It should be noted that the quantities noted in the schedule for doors, windows and ventilators are inside clear dimensions.

15. Works should be executed in general as per Marryat's specifications.

16. Contractors should make their own arrangements for the supply of water.

Schedule.

Sl. No.	Details of work	Unit	Quantity
1	Earthwork excavating for foundation in all soils including hard rock, if any, filling in the basement in 6" layers including watering and consolidating charges, conveying the surplus spoil to places shown by the department up to a maximum lead of 700 feet and spreading it evenly as per levels fixed by the Department	1,000 C.ft.	2,100 C.ft.
2	Concrete broken stone in sand mortar	100 ,,	1,200 ,,
3	Coursed rubble masonry in sand mortar, first class, including bond stones and dressing corner stones of walls ..	100 ,,	1,000 ,,
4	Burnt brick in prepared mud	100 ,,	4,300 ,,
5	Burnt brick in sand mortar	100 ,,	1,000 ,,
6	Archwork, burnt brick in sand mortar including centering charges	100 ,,	70 ,,
7	Supplying and fixing in sand mortar, burnt stone slabs 6 thick roughly dressed	S.ft.	290 S.ft.
8	Do do two lines dressed on top, faces and edges rounded off	,,	180 ,,
9	Cutting grooves in 6" thick burnt stone slabs	Each	26
10	Cement concrete slabs including necessary wooden framework for laying concrete, hoisting and fixing in position and fixing of bolts	100 C.ft.	170 C.ft.
11	Supplying teakwood trusses for 16 ft. clear span as per design of the trusses in the Works Superintendent's Office, hoisting and fixing in position including two coats of wood oiling and silicate painting of all iron work	Each	6
12	Conveying 41¼ lbs. section rails from Stores, cutting, drilling holes, hoisting and fixing in position including two coats of silicate painting	R.ft.	320 R.ft.
13	Teakwood wrought and put up including two coats of woodoiling	C.ft.	160 C.ft.
14	Roofing with pucca terrace	100 S.ft.	320 S.ft.
15	Roofing with first class Mangalore pattern Yelahanka tiles over 2"×1" teak reepers including chunam borders, etc., complete	100 ,,	2,800 ,,
16	Supplying Mangalore pattern Yelahanka ridge tiles and setting in cement mortar	R.ft.	220 R.ft.
17	Plain masonry parapet wall as per design of the parapet wall of the Works Superintendent's Office	,,	40 ,,
18	Burnt brick in mortar masonry cornice including cement plastering 9"×9"	R.ft.	10 R.ft.
19	Burnt brick in mortar masonry cornice including cement plastering 6"×6"	,,	22 ,,
20	Burnt brick in mortar masonry cornice including cement plastering 3"×3"	,,	54 ,,
21	Supplying and fixing 22 B. W. G. galvanised iron valley sheets including teakwood planking 1" thick including two coats of woodoiling of planking	S.ft.	200 S.ft.
22	Supplying and fixing teakwood eaves-board including silicate painting as per design of the Works Superintendent's Office	R.ft.	240 R.ft.
23	Chunam plastering	100 S.ft.	10,600 S.ft.
24	Chunam pointing	100 ,,	500 ,,
25	Cement plastering ½" thick	100 S.ft.	120 S.ft.
26	White and colour washing two coats	100 ,,	11,100 ,,

Sl. No.	Details of work	Unit	Quantity
27	Teakwood panelled doors, as per specifications including brass hasps and staples, brass handles, wooden stoppers, etc., complete	S.ft.	257 S.ft.
28	Teakwood windows with panelled shutters outside and 1" diameter iron bars and glazed shutters inside including Parliamentary hinges, brass handles, etc. complete	,,	212 ,,
29	Teakwood glazed ventilators with one inch diameter iron bars as per sample	,,	68 ,,
30	Flooring with $\frac{3}{4}$" cement plastering over 6" thick cement broken stone in (mortar) bed	100 ,,	1,850 ,,
31	Silicate painting two coats	100 ,,	1,650 ,,
32	Teakwood pendants	Each	10
33	Supplying and fixing cast iron down water pipes including bends, head, shoes, etc., complete including silicate painting	R.ft.	25 R.ft.
	For item No. 30 rates are also to be quoted for 'Flooring with 4" thick burnt stone slabs two lines dressed over 6" thick concrete (broken stone in sand mortar) bed including cement pointing'. The size and fixing of the slabs are to be as per approved plan	100 S.ft.	1,850 S.ft.

N.B.—(1) Cement, silicate paint, and linseed oil required for the work will be supplied by the Department.

(2) R. M. Certificates will be given for conveying tiles from Yelahanka.

R. N. MIRZA,
Senior Executive Engineer.

PRIVATE ADVERTISEMENTS

IN THE COURT OF THE DISTRICT JUDGE AT BANGALORE DIVISION, BANGALORE.

Insolvency Application No. 7 of 1935-36.

D. R. Gundappa, Hotel-keeper, Chikballapur .. .. *Petitioner.*

vs.

(1) Chikballapur Co-operative Society, (2) Veerasettappa, (3) S. Ramachandra Rao, (4) Puttasamappa, (5) Doddamuguvalappa, (6) Kankanti Venkatapathappa, (7) Gare Venkatasamy, (8) Nema Anantharamaiya Setty, (9) Olety Venkatachalapathy, (10) Ramachar, (11) M. Chikkachinnappa, (12) M. Hotel Subbanna, (13) The Manager, the Bank of Mysore at Chikballapur, (14) Chatram Kaliandas & Co., (15) Hanumappa *alias* Thayappa, (16) Yelahankada Rangappa, (17) Bangalore City Co-operative Bank, Ltd., (18) Kota Kamakshiah, (19) D. Gundu Rao .. .. *Opponents.*

Whereas the abovenamed petitioner has applied to this Court, by a petition, dated 20th day of January 1936, to be declared an insolvent under the Mysore Insolvency Regulation, VI of 1911, and your names appear in the list of creditors filed by the aforesaid debtor, this is to give you notice that the Court has fixed the 10th day of September 1936, for the hearing of the aforesaid petition and the examination of the debtor. If you desire to be represented in the matter you should attend in person or by duly instructed pleader.

Given under my hand and the seal of the Court, this 10th day of August 1936.